PROJECT :
LOCATION :
SUBJECT : **Bill of Materials**
DATE : **JUNE 3, 2022**

| | |
|---|---|
| **Gross Area** | **2,138.43** |
| **Net Area** | **2,036.08** |
| **Total Cost** | **35,847,245.04** |
| **Cost / sqm ( Net )** | **17,606.02** |
| **Cost / sqm ( Gross )** | **16,763.34** |

| ITEM NO. | WORK ITEM | QTY | UNIT | UNIT COST | | | | TOTAL AMOUNT |
|---|---|---|---|---|---|---|---|---|
| | | | | MATERIALS | AMOUNT | LABOR | AMOUNT | |
| **I.** | **GENERAL REQUIREMENTS** | | | | | | | |
| 1.0 | Mobilization / Demobilization | 1.00 | lot | | - | 150,000.00 | 150,000.00 | 150,000.00 |
| 2.0 | Temporary Facilities | 1.00 | lot | 120,000.00 | 120,000.00 | 35,000.00 | 35,000.00 | 155,000.00 |
| 3.0 | Temporary Utilities | 14.00 | mos | | - | 25,000.00 | 350,000.00 | 350,000.00 |
| 4.0 | Building Permit / Occupancy Permit | **- BY OWNER -** | | | | | | |
| 5.0 | Bonds & Insurance ( CARI / Performance Bond ) | **- BY OWNER -** | | | | | | |
| 6.0 | Staff & Supervision | 14.00 | mos | | - | 45,000.00 | 630,000.00 | 630,000.00 |
| 7.0 | Temporary Site Enclosure / Fence | 1.00 | lot | 75,000.00 | 75,000.00 | 25,000.00 | 25,000.00 | 100,000.00 |
| | **Sub-Total:** | | | | | | | **1,385,000.00** |
| **II.** | **BUILDING** | | | | | | | |
| 1.0 | **EARTHWORKS** | | | | | | | |
| | Excavation | 119.31 | cum | | - | 450.00 | 53,687.48 | 53,687.48 |
| | Trimming | 21.96 | sqm | | - | 100.00 | 2,196.00 | 2,196.00 |
| | Backfill & Compaction | 81.88 | cum | | - | 280.00 | 22,925.40 | 22,925.40 |
| | Dewatering | 1.00 | lot | 20,000.00 | 20,000.00 | 19,800.00 | 19,800.00 | 39,800.00 |
| | Haul out of Unsuitable Materials | 43.04 | cum | | - | 450.00 | 19,369.55 | 19,369.55 |
| | **Sub-Total:** | | | | | | | **137,978.42** |
| 2.0 | **CIVIL WORKS** | | | | | | | |
| | Layout & Staking | 1.00 | lot | 25,000.00 | 25,000.00 | 15,000.00 | 15,000.00 | 40,000.00 |
| | Gravel Bedding | 43.63 | cum | 1,100.00 | 47,987.92 | 280.00 | 12,215.11 | 60,203.02 |
| | Vapor Barrier | 392.62 | sqm | 50.00 | 19,631.17 | 6.00 | 2,355.74 | 21,986.91 |
| | Soil Poisoning | 414.58 | sqm | 60.00 | 24,875.01 | 6.00 | 2,487.50 | 27,362.51 |
| | **Sub-Total:** | | | | | | | **149,552.44** |
| 3.0 | **BORE PILING WORKS** | | | | | | | |
| | General Requirements | 1.00 | lot | | - | 277,000.00 | 277,000.00 | 249,300.00 |
| | Drilling Works with provision for temporary Steel Casing | 638.00 | lm | | - | 4,500.00 | 2,871,000.00 | 2,583,900.00 |
| | Fabrication & Installation of Rebar Cages | 16,240.00 | kgs | 60.00 | 974,400.00 | 6.00 | 97,440.00 | 964,656.00 |
| | Ready Mixed Concrete by Tremie Method | 116.00 | cum | 6,000.00 | 696,000.00 | 900.00 | 104,400.00 | 720,360.00 |
| | Pile Integrity Test (PIT) & Pile Dynamic Test (PDA) | 2.00 | pos | | | 150,000.00 | 300,000.00 | 270,000.00 |
| | Haulout of Excavated Materials Off-Site | 168.00 | TL | | | 2,000.00 | 336,000.00 | 302,400.00 |
| | Pile Hacking | 29.00 | pcs | | | 500.00 | 14,500.00 | 13,050.00 |
| | **Sub-Total:** | | | | | | | **5,103,666.00** |
| 4.0 | **STRUCTURAL WORKS** | | | | | | | |
| | a. Ready Mixed Concrete | **678.12** | **cum** | | | | | |
| | Footing ( 4,000psi @ 28days ) | 18.45 | cum | 4,450.00 | 82,086.48 | 500.00 | 9,223.20 | 91,309.68 |
| | Slab On Grade ( 3,000psi @ 28days ) | 52.30 | cum | 4,250.00 | 222,288.35 | 250.00 | 13,075.79 | 235,364.13 |
| | FTB ( 4,000psi @ 28days ) | 18.98 | cum | 4,450.00 | 84,472.96 | 500.00 | 9,491.34 | 93,964.30 |
| | Columns ( 4,000psi @ 28days ) | 108.29 | cum | 4,450.00 | 481,874.93 | 500.00 | 54,143.25 | 536,018.18 |
| | Beams ( 4,000psi @ 28days ) | 195.92 | cum | 4,450.00 | 871,829.54 | 250.00 | 48,979.19 | 920,808.73 |
| | Suspended Slab ( 4,000psi @ 28days ) | 244.96 | cum | 4,450.00 | 1,090,055.31 | 250.00 | 61,239.06 | 1,151,294.38 |
| | RC Stairs ( 4,000psi @ 28days ) | 13.82 | cum | 4,450.00 | 61,500.78 | 500.00 | 6,910.20 | 68,410.98 |
| | Cistern Tank / Fire Tank / Septic Tank ( 4,000psi @ 28days ) | 25.41 | cum | 4,450.00 | 113,074.50 | 500.00 | 12,705.00 | 125,779.50 |
| | b. Rebars ( Steel Asia Only) | **124,208.98** | **kgs** | | | | | |
| | Footing | 3,394.53 | kgs | 54.69 | 185,646.63 | 6.00 | 20,367.16 | 206,013.78 |
| | Slab On Grade | 322.19 | kgs | 54.69 | 17,620.43 | 6.00 | 1,933.12 | 19,553.55 |
| | FTB | 4,923.58 | kgs | 54.69 | 269,270.49 | 6.00 | 29,541.47 | 298,811.96 |
| | Columns | 29,648.25 | kgs | 54.69 | 1,621,462.63 | 6.00 | 177,889.48 | 1,799,352.11 |
| | Beams | 50,879.59 | kgs | 54.69 | 2,782,604.64 | 6.00 | 305,277.52 | 3,087,882.16 |
| | Suspended Slab | 29,394.75 | kgs | 54.69 | 1,607,598.88 | 6.00 | 176,368.50 | 1,783,967.38 |
| | RC Stairs | 2,487.67 | kgs | 54.69 | 136,050.78 | 6.00 | 14,926.03 | 150,976.81 |
| | Cistern Tank / Fire Tank / Septic Tank | 3,158.44 | kgs | 54.69 | 172,734.82 | 6.00 | 18,950.61 | 191,685.43 |
| | Ga#16 GI Tie Wire | 62.10 | rolls | 1,650.00 | 102,472.41 | | - | 102,472.41 |
| | c. Formworks | **5,202.65** | **sqm** | | | | | |
| | Footing | 59.04 | sqm | 350.00 | 20,664.00 | 240.00 | 14,169.60 | 34,833.60 |
| | Slab On Grade | 2.25 | sqm | 350.00 | 788.29 | 240.00 | 540.54 | 1,328.83 |
| | FTB | 144.63 | sqm | 350.00 | 50,620.50 | 240.00 | 34,711.20 | 85,331.70 |
| | Columns | 950.25 | sqm | 350.00 | 332,587.50 | 240.00 | 228,060.00 | 560,647.50 |
| | Beams | 1,795.87 | sqm | 350.00 | 628,555.73 | 240.00 | 431,009.64 | 1,059,565.37 |
| | Suspended Slab | 1,870.58 | sqm | 350.00 | 654,701.25 | 240.00 | 448,938.00 | 1,103,639.25 |
| | RC Stairs | 87.12 | sqm | 350.00 | 30,492.00 | 240.00 | 20,908.80 | 51,400.80 |
| | Cistern Tank / Fire Tank / Septic Tank | 292.91 | sqm | 350.00 | 102,516.75 | 240.00 | 70,297.20 | 172,813.95 |
| | d. Smooth Trowel Finish | 2,138.43 | sqm | | | 50.00 | 106,921.52 | 106,921.52 |
| | e. Roof Framing Works | 2,475.25 | kgs | 65.00 | 160,891.05 | 12.00 | 29,702.96 | 190,594.02 |
| | f. Ga#24 Long Span Roofing | 202.40 | sqm | 900.00 | 182,160.00 | 220.00 | 44,528.00 | 226,688.00 |
| | **Sub-total:** | | | | | | | **14,457,430.01** |

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 5.0 | **ARCHITECTURAL WORKS** | | | | | | | |
| **A.** | **Masonry Works** | | | | | | | |
| | 6" CHB Laying 700psi | 2,332.92 | sqm | 650.00 | 1,516,396.08 | 150.00 | 349,937.56 | 1,866,333.63 |
| | 8" CHB Laying 1000psi | 260.12 | sqm | 1,100.00 | 286,127.82 | 200.00 | 52,023.24 | 338,151.06 |
| | Stiffener / Lintel Beam | 1,049.16 | lm | 845.00 | 886,543.01 | 230.00 | 241,307.56 | 1,127,850.57 |
| | Exterior Wall Plastering ( including gondola / scaffoldings ) | 1,563.23 | sqm | 200.00 | 312,645.17 | 250.00 | 390,806.46 | 703,451.63 |
| | Interior Wall Plastering | 3,641.26 | sqm | 200.00 | 728,252.64 | 140.00 | 509,776.85 | 1,238,029.49 |
| | Lineal Plastering | 1,298.40 | sqm | | - | 50.00 | 64,920.00 | 64,920.00 |
| **B.** | **Floor Finishes** | | | | | | | |
| | 2" thick Concrete Floor Topping | 269.63 | sqm | 200.00 | 53,926.32 | 150.00 | 40,444.74 | 94,371.06 |
| | 30 x 30 Unglazed Granite Floor Tiles @ T&B | 30.03 | sqm | 750.00 | 22,524.08 | 220.00 | 6,607.06 | 29,131.14 |
| | 60 x 60 Granite Polish Tiles @ Penthouse | 89.08 | sqm | 750.00 | 66,810.08 | 220.00 | 19,597.62 | 86,407.70 |
| | 60 x 60 Unglazed Floor Tiles @ View Deck | 220.00 | sqm | 750.00 | 165,000.00 | 220.00 | 48,400.00 | 213,400.00 |
| | Plain Cement Finish with Hardener on stair | 87.12 | sqm | 460.00 | 40,075.20 | 220.00 | 19,166.40 | 59,241.60 |
| | Plain Cement Finish with Concrete hardener @ Warehouse Area | 1,674.33 | sqm | 180.00 | 301,379.40 | | - | 301,379.40 |
| | Others: | | | | | | | |
| **C.** | **Wall Finishes** | | | | | | | |
| | 30 x 30 Granite Wall Tiles @ T&B | 148.18 | sqm | 750.00 | 111,132.00 | 250.00 | 37,044.00 | 148,176.00 |
| | Others: | | | | | | | |
| **D.** | **Ceiling Finishes** | | | | | | | |
| | Rubbed Concrete on Slab & Beam Soffit | 1,674.33 | sqm | 75.00 | 125,574.75 | 50.00 | 83,716.50 | 209,291.25 |
| | 12mm MR Gypsum Board on metal furring | 140.40 | sqm | 600.00 | 84,239.82 | - included - | | 84,239.82 |
| | Others: | | | | | | | |
| **E.** | **Doors, Jambs & Hardwares** | | | | | | | |
| | SFD-1 (Steel Fire Door 90 x 210cm ) | 6.00 | set | 11,406.00 | 68,436.00 | 1,500.00 | 9,000.00 | 77,436.00 |
| | SFD-2 (Steel Flush Door 80 x 210cm ) | 10.00 | set | 10,272.00 | 102,720.00 | 1,500.00 | 15,000.00 | 117,720.00 |
| | PVCD-1 ( Pvc Flush Door 60 x 210cm ) | 7.00 | set | 2,800.00 | 19,600.00 | 1,200.00 | 8,400.00 | 28,000.00 |
| | SFD-3 ( Double Swing Steel Flush Door 180 x 210cm ) | 1.00 | set | 22,812.00 | 22,812.00 | 2,200.00 | 2,200.00 | 25,012.00 |
| | SFD-4 ( Steel Flush Door 90 x 210cm ) | 1.00 | set | 11,406.00 | 11,406.00 | 1,500.00 | 1,500.00 | 12,906.00 |
| | RUD-1 ( Manual Roll Up Door 560 x 735cm ) | 1.00 | set | 185,220.00 | 185,220.00 | - included - | | 185,220.00 |
| **F.** | **Windows** | | | | | | | |
| | AAW 1 ( 3.65 x 0.70m Aluminum Awning Window ) | 18.00 | set | 12,264.00 | 220,752.00 | - included - | | 220,752.00 |
| | AAW 2 ( 3.10 x 0.70m Aluminum Awning Window ) | 3.00 | set | 10,416.00 | 31,248.00 | - included - | | 31,248.00 |
| | AAW 3 ( 2.60 x 0.70m Aluminum Awning Window ) | 2.00 | set | 8,736.00 | 17,472.00 | - included - | | 17,472.00 |
| | AAW 4 ( 2.10 x 0.70m Aluminum Awning Window ) | 3.00 | set | 7,056.00 | 21,168.00 | - included - | | 21,168.00 |
| | AAW 5 ( 0.60 x 0.70m Aluminum Awning Window ) | 14.00 | set | 2,016.00 | 28,224.00 | - included - | | 28,224.00 |
| | AAW 6 ( 1.60 x 0.70m Aluminum Awning Window ) | 1.00 | set | 5,376.00 | 5,376.00 | - included - | | 5,376.00 |
| **G.** | **Painting Works** | | | | | | | |
| | Exterior Walls | 1,563.23 | sqm | 480.00 | 750,348.41 | - included - | | 750,348.41 |
| | Interior Walls | 3,493.09 | sqm | 260.00 | 908,202.67 | - included - | | 908,202.67 |
| | Latex Paint on Ceiling | 1,814.73 | sqm | 260.00 | 471,829.72 | - included - | | 471,829.72 |
| | Metal Doors & Jambs | 94.58 | sqm | 480.00 | 45,397.44 | - included - | | 45,397.44 |
| **H.** | **Waterproofing works** | | | | | | | |
| | Capillary Type on Toilet & Bath | 27.60 | sqm | 420.00 | 11,591.58 | - included - | | 11,591.58 |
| | Capillary Type on Open Deck | 246.51 | sqm | 420.00 | 103,534.20 | - included - | | 103,534.20 |
| | Epoxy Tank Lining on Cistern Tank & Fire Tank | 88.20 | sqm | 950.00 | 83,790.00 | - included - | | 83,790.00 |
| **I.** | **Miscellaneous Steel Works** | | | | | | | |
| | Steel Stair Railing painted finish | 75.00 | lm | 1,500.00 | 112,500.00 | - included - | | 112,500.00 |
| | Steel Fire Exit Stair | 25.00 | lm | 6,500.00 | 162,500.00 | - included - | | 162,500.00 |
| | 2 x 2 x 4mm Angle Bar Stair Nosing | 385.00 | lm | 450.00 | 173,250.00 | - included - | | 173,250.00 |
| | Stainless Water Tank ( 3,000 gallons capacity ) | 1.00 | sets | 180,000.00 | 180,000.00 | - included - | | 180,000.00 |
| | **Sub-total:** | | | | | | | **10,337,852.37** |
| **6.0** | **Electrical Works** | **1.00** | **lot** | 1,710,306.32 | 1,710,306.32 | - included - | | 1,710,306.32 |
| **7.0** | **Plumbing & Sanitary Works ( including Toilet Fixtures)** | **1.00** | **lot** | 1,140,204.21 | 1,140,204.21 | - included - | | 1,140,204.21 |
| **8.0** | **FirePro Works** | **1.00** | **lot** | 1,425,255.27 | 1,425,255.27 | - included - | | 1,425,255.27 |
| | **TOTAL BID AMOUNT ( VAT EXCLUSIVE )** | | | | | | | **35,847,245.04** |

PREPARED & SUBMITTED BY,
**MEGACON BUILDERS CORPORATION**
By:

**Mark Christian P. Belila**
Project Engineer

Project :
Location :
Subject : **SUMMARY OF REBAR REQUIREMENT**

Date **as of Dec 14,2022**

| | | |
|---|---|---|
| **DELVERED** | **89,855.39** | **KGS** |
| **BALANCE** | **19,827.57** | **KGS** |

| Item no. | Description | QTY | Unit Weight (kgs) | Total Weight (kgs) |
|---|---|---|---|---|
| **1.0** | **FOUNDATION** | | | |
| | **a. Grade 60** | | | |
| | 20mm x 10.50m | 14 | 25.9 | 362.52 |
| | 20mm x 7.50m | 112 | 18.5 | 2,071.57 |
| | | | | |
| | 16mm x 7.50m | 31 | 11.8 | 362.15 |
| | **a. Grade 40** | | | |
| | 12mm x 12.0m | 13 | 10.656 | 138.53 |
| | **subtotal:** | | | **2,934.77** |
| **2.0** | **CISTERN TANK** | | | |
| | **a. Grade 60** | | | |
| | 16mm x 10.50m | 10 | 16.569 | 165.69 |
| | 16mm x 6.0m | 123 | 9.468 | 1,159.83 |
| | | | | |
| | **a. Grade 40** | | | |
| | 12mm x 12.0m | 57 | 10.656 | 610.06 |
| | **subtotal:** | | | **1,935.58** |
| **3.0** | **FOOTING TIE BEAMS** | | | |
| | **a. Grade 60** | | | |
| | 25mm x 12.0m | 21 | 46.2 | 971.21 |
| | 25mm x 10.50m | 11 | 40.5 | 445.14 |
| | 25mm x 9.0m | 33 | 34.7 | 1,144.64 |
| | 25mm x 7.50m | 38 | 28.9 | 1,098.39 |
| | 25mm x 6.0m | 6 | 23.1 | 138.74 |
| | **a. Grade 40** | | | |
| | 10mm x 12.0m | 84 | 7.4 | 620.93 |
| | **subtotal:** | | | **4,419.05** |
| **4.0** | **2F SUSPENDED BEAMS & GIRDERS** | | | |
| | **a. Grade 60** | | | |
| | 25mm x 12.0m | 31 | 46.248 | 1,449.10 |
| | 25mm x 10.5m | 35 | 40.467 | 1,396.11 |
| | 25mm x 9.0m | 51 | 34.686 | 1,751.64 |
| | 25mm x 7.50m | 50 | 28.905 | 1,450.07 |
| | 25mm x 6.0m | 10 | 23.124 | 231.24 |
| | | | | |
| | 20mm x 12.0m | 3 | 29.594 | 88.78 |
| | 20mm x 10.5m | 29 | 25.895 | 741.08 |
| | 20mm x 9.0m | 16 | 22.195 | 355.13 |

| | | | | |
|---|---|---|---|---|
| | 20mm x 7.50m | 27 | 18.496 | 496.31 |
| | 20mm x 6.0m | 13 | 14.797 | 192.36 |
| | **b. Grade 40** | | | |
| | 12mm x 12.0m | 1654 | 10.656 | 17,619.81 |
| | 10mm x 12.0m | 241 | 7.4 | 1,780.00 |
| | **subtotal:** | | | **27,551.63** |
| **5.0** | **3F-5F SUSPENDED BEAMS & GIRDERS** | | | |
| | **a. Grade 60** | | | |
| | 25mm x 12.0m | - | 46.2 | - |
| | 25mm x 10.5m | - | 40.5 | - |
| | 25mm x 9.0m | 258 | 34.7 | 8,948.99 |
| | 25mm x 7.50m | 210 | 28.9 | 6,070.05 |
| | 25mm x 6.0m | 24 | 23.1 | 554.98 |
| | | | | |
| | 20mm x 12.0m | - | - | - |
| | 20mm x 10.5m | | 25.9 | - |
| | 20mm x 9.0m | 81 | 22.2 | 1,797.83 |
| | 20mm x 7.50m | 132 | 18.5 | 2,441.49 |
| | 20mm x 6.0m | 57 | 14.8 | 843.43 |
| | **b. Grade 40** | | | |
| | 12mm x 12.0m | 1002 | 10.7 | 10,680.00 |
| | 10mm x 12.0m | 722 | 7.4 | 5,340.00 |
| | **subtotal:** | | | **36,676.76** |
| **6.0** | **)OFDECK SUSPENDED BEAMS & GIRDERS** | | | |
| | **a. Grade 60** | | | |
| | 25mm x 12.0m | 14 | 46.248 | 647.47 |
| | 25mm x 10.5m | 20 | 40.467 | 809.34 |
| | 25mm x 9.0m | 26 | 34.686 | 901.84 |
| | 25mm x 7.50m | 18 | 28.905 | 520.29 |
| | 25mm x 6.0m | 6 | 23.124 | 138.74 |
| | | | | |
| | 20mm x 12.0m | | 0.000 | - |
| | 20mm x 10.5m | 22 | 25.895 | 569.68 |
| | 20mm x 9.0m | 15 | 22.195 | 332.93 |
| | 20mm x 7.50m | 26 | 18.496 | 480.90 |
| | 20mm x 6.0m | 18 | 14.797 | 266.34 |
| | **b. Grade 40** | | | |
| | 12mm x 12.0m | 334 | 10.656 | 3,560.00 |
| | 10mm x 12.0m | 241 | 7.392 | 1,780.00 |
| | **subtotal:** | | | **10,007.54** |
| **7.0** | **RC. WALL / RC COLUMNS (FTG - 2F = 12 SETS)** | | | |
| | **a. Grade 60** | | | |
| | 28mm x 9.0m | 11.0 | 43.5 | 478.53 |
| | 28mm x 7.50m | 11.0 | 36.3 | 398.78 |
| | | | | |
| | 25mm x 10.50m | 22.0 | 40.5 | 890.27 |
| | 25mm x 9.0m | 82.0 | 34.7 | 2,844.25 |

| | | | | |
|---|---|---|---|---|
| | 25mm x 7.50m | 68.0 | 28.9 | 1,965.54 |
| | 25mm x 6.0m | 20.0 | 23.1 | 462.48 |
| | | | | |
| | 20mm x 10.50m | 0.0 | 25.9 | - |
| | 20mm x 9.0m | 15.0 | 22.2 | 332.93 |
| | 20mm x 7.50m | 126.0 | 18.5 | 2,330.52 |
| | 20mm x 6.0m | 60.0 | 14.8 | 887.82 |
| | | | | |
| | 16mm x 9.0m | 42.0 | 14.2 | 596.48 |
| | 16mm x 7.50m | 56.0 | 11.8 | 662.76 |
| | 16mm x 6.0m | 48.0 | 9.5 | 454.46 |
| | **b. Grade 40** | | | |
| | 12mm x 12.0m | 1300.0 | 10.7 | 13,852.80 |
| | **subtotal:** | | | **26,157.63** |
| | | | | |
| | **GRAND TOTAL WEIGHT** | | | **109,682.96** |

Prepared By,

**Mark Christian Belila**
Project Engineer

**Project :**
**Location :**
**Owner :**
**Subject : BOQ (ARCH)**

| Item# | Description | Quantity | Unit |
|---|---|---|---|
| **I.** | **ARCHITECTURAL WORKS** | | |
| 1.0 | **GROUND FLOOR - 2F:** | | |
| | CHB 6" Laying | 2,332.92 | sqm |
| | - CHB 6 ( 400psi ) | 29,161.46 | pcs |
| | - Cement in bags (40kgs) | 1,633.04 | bags |
| | - White Sand | 179.63 | cum |
| | CHB 8" Laying | 260.12 | sqm |
| | - CHB 4 ( 400psi ) | 3,251.45 | pcs |
| | - Cement in bags (40kgs) | 241.91 | bags |
| | - White Sand | 26.53 | cum |
| | Stiffener/lintel | 1,049.16 | lm |
| | - Volume | 0.96 | cum |
| | - Cement in bags (40kgs) | 7.68 | bags |
| | - White Sand | 0.41 | cum |
| | - Gravel | 0.62 | cum |
| | Exterior Plastering Works | 1,563.23 | sqm |
| | - Cement in bags (40kgs) | 547.13 | bags |
| | - White Sand | 59.09 | cum |
| | Interior Plastering Works | 3,641.26 | sqm |
| | - Cement in bags (40kgs) | 1,274.44 | bags |
| | - White Sand | 137.64 | cum |
| | Linear Plastering Works | 1,298.40 | lm |
| | Rubbed Concrete Works: | | |
| | -Slab & beams soffit | 1,674.33 | sqm |
| | | | sqm |
| | Painting Works | | |
| | -Ceiling | 1,814.73 | sqm |
| | -Neutralizer | 39.92 | gal |
| | -Skimcoat (20kg) | 49.91 | bags |
| | -Primer | 79.85 | gal |
| | -Semi-gloss | 159.70 | gal |
| | - Exterior walls | 1,563.23 | sqm |
| | -Neutralizer | 34.39 | gal |
| | -Primer | 68.78 | gal |
| | -Waterproofing | 137.56 | gal |
| | - Interior Walls | 3,493.09 | sqm |
| | -Neutralizer | 76.85 | gal |
| | -Skimcoat (20kg) | 96.06 | bags |
| | -Primer (Flat Latex 701) 16L | 38.42 | pale |
| | -Semi-gloss | 307.39 | gal |
| | - Metal Doors & jamb | 94.58 | sqm |
| | Description | QTY | UNIT |
| | - 40 x 40 Unglazed Ceramic Floor Tiles @ T&B | 105.59 | PCS |
| | - 40 x 40 Glazed Ceramic Wall Tiles @ T&B | 344.40 | PCS |
| | - Tile adhesive | 36.00 | BAGS |